BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/OW/WORK_INDENT16513

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/08/2014-15, Date: 30.12.2014

Park Maintenance inWard No. 08, Kodigehalli Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of TARANATH K R	
				In Figures	In Words
1	225	Clearing and grubbing land including uprooting rank vegetation, grass, brush, shrubs, saplings and trees of girth upto 300mm by manual means in area of light jungle, removal of stumps, disposal of unserviceable materials, stacking of serviceable materials, labour charges compelte as per specifications.	cum	5.88	Rupees Five and Eighty Eight Paise Only
2	4	Providing Children Play Two Seater Standard SWing Equipment: This sWing' consist of 2 Nos. seats of solid metal seats powder coated of Size-500mmx 250mm x 16 SWG supported by MS chains of Length 1.8mtrs, each seat is suspended by 1 line of chain. The chains are supported by circular housingswith bearing from which the chain in suspended. The beam is of 50mm MS tAt class pipe. Size of MS • chain 30mm x 20mm x 5mm thick, the length of the main beam is 2.40 mtrs and No. 1 24800.00 25300.00 28400.00 24000.00 -263.00.00 *·Lowestheight 2.00mtrs. The 2 Nos of cost iron-heads. Four footing are in 42mm pipes. All pipes are of ISI grade. All the pipes are painted with two coats of superset paint over a coat of protective Zinc chromate yellow oxide including fiXing the play equipments in CC 1:2:4, curing etc., complete with all lead, lift. loading. unloading and any other incidental charges and as per the drawing and specification and directionof the Engineerin chargeof the work.. 2lp	No.	23976.0	Rupees Twenty Three Thousand Nine Hundred Seventy Six Only
3	4	2lprovldlng Children Play Standard See Saw Seater Equipment: This equipmentis made up of main beam 50mmMS pipe tAt class of length 1.98 mtr.-With two handles welded at the ends as a hand are made of 20mm tA' class pipe. The main beam is pivoted to the'bottomsupports of 40mm MS pipes by bush bearing clamped by pivot' 1 1 ,.. 1 1 **joints which swivel over 28mm Dia steel shaft. which gets installed in the ground byl ' 'I 14900.00 15800.00 14000.00 .1 11800.00 'I 16200.00 I ** Lowestmeans of concrete, 2 nos. seats are made of 250mm x 200mm x 18 SWG MS-No. sheets with T hand rest at the front. Air pipes are of ISI grade. All the pipes'are . ~ painted with two coats of super set paint over a coat of protective Zinc chromate yellow oxide including fixing the play equlpments in CC 1:2:4. curing etc., complete with all lead, lift, loading, unloading and any other incidentalcharge$-:8nd as per the draWing and specification and directionof the Engineerin charge of the work.	No.	13986.0	Rupees Thirteen Thousand Nine Hundred Eighty Six Only

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

4	4	Providing Children Play Merry-Go-Round Equipment: Made of MS. 'A' class pipes. Main pillars are in 100mm, fitted with shaft and two bearings and other cross members are in 25 & 20mm MA 'A' Class pipes, bottom ring is made out of 25mm 0 ring size is 1.20 mtrs Dia, fitted with four seats are in mental sats of 250 x 200 x 18SGE, handles are made out of 20mm NB pipes and other supports are in 25mm MS 'N class pipes. All the pipes are painted with two coats of super set paint over a coat of protective Zinc chromate yellow including fixing the play equipments in CC 1:2:4, curing etc., complete with all lead, lift, loading, unloading and any other incidental charges and as per the drawing and specification and direction of the EnQlneer In enarce of the work	No.	27972.0	Rupees Twenty Seven Thousand Nine Hundred Seventy Two Only
5	4	pro~Mjng Children Play Two Seater Swing Duck Equipment: This swing consist of 2 Nos. FRP Ducks supported by MS chains of Length 1.05mtrs, each duck Is suspended by 3 lines of chains. The chains are supported by circular housings with bearing from which the chain in suspended. The main beam is of 42mm MS 'A' class pipe. Size of MS chain 30mm x 20mm x 5mm thick, the length of the main beam is 2.40 mtrs and height 1.95mtrs. Four footing are in 42mm pipes. All pipes are of ISI grade. All the pipes are painted with two coats of super set paint over a coat 0 protective Zinc chromate yellow oxide including fixing the play equipments in CC 1:2:4, curing etc., complete with all lead, lift, loading, unloading and any other incidental charges and as per the drawing and specification and direction of the Enalneer in charae of the work.	No.	27972.0	Rupees Twenty Seven Thousand Nine Hundred Seventy Two Only
6	4	Providing Children Play Main Wheel Equipment: Made of MS 'A' class pipes. Main pillars are in 100mm Dia, fitt~d with shaft and two bearings and other cross members are in 25 & 20mm Ms 'A' Class pipes, the bottom ring is made out 0 32mm NB pipes and 1.20 mtrs Dla, the bottom sheet is CR 16SWG.AII the pipesare painted with two coats of super set paint over a coat of protectlveZinc chromate yellow oxide including fixing the play equipments In CC 1:2:4, curing etc., complete with all lead, lift, loading,.unloading and any other incidental charges and as per the drawing and specification and direction of the Engineer in charge.of the work.	No	21978.0	Rupees Twenty One Thousand Nine Hundred Seventy Eight Only
7	4	Providing Children Play Standard Slide Equipment: Made out of M.S. 'A' class plpes:-Main frame are in 25mm and other railings are in 20mm, 1.5mtrs h x 3.00mtrs long x 0.45mtrs width, Sliding surface fitted with S.S. Sheet. All pipes are of ISI grade. All the pipes are painted with two coats of super set paint over a coat 0 protective Zinc chromate yellow oxide including fixing the play equipments in CC 1:2:4, curing etc., complete with all lead, lift, loading, unloading and any other Incidental charges and as per the drawing and specification and direction of the Enalneer in charce of the work.	NO.	27972.0	Rupees Twenty Seven Thousand Nine Hundred Seventy Two Only
8	10	Providing Sitting chairs made of RCC including steel reinforcement as per the directions of the Engineer-in-charge of the work	No.	5994.0	Rupees Five Thousand Nine Hundred Ninety Four Only

Executive Engineer
Byatarayanapura Division
Yelahanka B.B.M.P.
Bangalore - 560 092

	36	2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications	Cum	143.73	Rupees One Hundred Forty Three and Seventy Three Paise Only
10	3.84	KSRB 2-2.1 : Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications	cum	176.0	Rupees One Hundred Seventy Six Only
11	3.07	KSRB 4-1.7 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.84 cum and fine aggregates @ 0.56 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	cum	5282.39	Rupees Five Thousand Two Hundred Eighty Two and Thirty Nine Paise Only
12	48	Supplying and Providing Sand	cum	1449.0	Rupees One Thousand Four Hundred Forty Nine Only
13	288	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 of size 450x200x400 mm and finished with CM 1:3 plastering and finishing cutting etc., complete	No.	357.5	Rupees Three Hundred Fifty Seven and Fifty Paise Only
14	38.4	Providinga and applying ready mix priming coat over ocncrete / masonry, / asbestos cement sheet / plastered surfaces incluдding preparing the surface after thorougly cleaning of oil, grease, dirt and other foreign matter and sand papering including cost of materials, labour compelte as per specifications	sqm	25.0	Rupees Twenty Five Only
15	38.4	Providing and applying spray painting in two coast (excluding priming coat) over ocncrete / masonry, / asbestos cement sheet / plastered surfaces incluдding preparing the surface after thorougly cleaning of oil, grease, dirt and other foreign matter and sand papering including cost of materials, labour compelte as per specifications	sqm	64.8	Rupees Sixty Four and Eighty Paise Only
16	1840	KSRB- 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications	sqm	82.0	Rupees Eighty Two Only

taranath

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92